ERNST HANSCH CONSTRUCTION LTD.

MCCC Parkade Booth Replacement

The Manitoba Centennial Centre required upgrades to its underground parkade to improve safety, replace dated components with more efficient systems and improve the exterior façade at the entrance to the parkade.

As the general contractor, Ernst Hansch Construction completed the upgrades which included replacement of the overhead doors with a new rapid roll overhead door system complete with controls and programming with the traffic control gate system. Prefinished aluminum wall panels were installed to complete the upgrades to the exterior façade.

The old parkade booth was demolished and a new security booth was constructed utilizing modern durable aluminum and glazing. Engineered shoring was installed to temporarily support the building during demolition of one of the main building columns. New permanent structural supports were installed along with a new window the exterior providing a clear line of sight to exterior vehicles from the parkade booth.

All work was completed while maintaining vehicle access into and out of the parkade for the duration of the project.

Client	Manitoba Centennial Centre Corporation
Location	555 Main Street, Winnipeg, Manitoba
Size	N/A
Completed	January 2011
Project Type	Commercial - Other Specialty
Services	Design-Bid-Build

AFTER

BEFORE